

R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208
DEERFIELD BEACH, FL 33442

PO BOX 162
MONTICELLO, NY 12701

TEL. (954)360-9496 FAX (954) 360-9326

PROJECT: WILLOW CREEK APARTMENTS

HARTFORD, CT

MARCH 2018

R & L #12764

MASTER RECAP. SHEET

SHEET NO. 1

OF NO. 4

| NO. | GENERAL DESCRIPTION | QUANTITY | UNIT LAB. | TOT. LAB. | UNIT MAT. | TOT. MAT. |
|-----|--|----------|-----------|-----------|-----------|-----------|
| | SITE CLEARING AND EARTHWORK | | | | | |
| 1 | visit site area to determine existing conditions allow | | ls | | | |
| 2 | protection work (from site visit) allow | | ls | | | |
| 3 | removal work | | | | | |
| | pavement | 520 | sf | | | |
| | walks | 150 | sf | | | |
| | bit curbs | 92 | lf | | | |
| | signs (salvage for reuse) | 4 | ea | | | |
| | note: all other demolition assumed to be already completed | | | | | |
| 4 | engineering and layout work allow | | ls | | | |
| 5 | clear and grub site area (5.6 ac) allow | | ls | | | |
| 6 | strip and stockpile topsoil | | | | | |
| | assume 6" 5.6 ac | 4512 | cy | | | |
| 7 | site excavation work | | | | | |
| | cut work | 944 | cy | | | |
| | fill work | 5213 | cy | | | |
| | graded area | 5.0 | ac | | | |
| 8 | building excavation work | | | | | |
| | general cut | 2778 | cy | | | |
| | trenching and footing | 2067 | cy | | | |
| | backfill work | | | | | |
| | exterior | 736 | cy | | | |
| | interior | 508 | cy | | | |
| | interior (to bring to subslab elevation and replace fill material) (structural fill) | 4185 | cy | | | |
| | graded area | 28500 | sf | | | |

R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208 PO BOX 162
 DEERFIELD BEACH, FL 33442 MONTICELLO, NY 12701
 TEL. (954)360-9496 FAX (954) 360-9326

PROJECT: WILLOW CREEK APARTMENTS
 HARTFORD, CT
 MARCH 2018
 R & L #12764

MASTER RECAP. SHEET

SHEET NO. 2

OF NO. 4

| NO. | GENERAL DESCRIPTION | QUANTITY | UNIT LAB. | TOT. LAB. | UNIT MAT. | TOT. MAT. |
|-----|--|----------|-----------|-----------|-----------|-----------|
| | SITE CLEARING AND EARTHWORK (CONT.) | | | | | |
| 9 | structural fill below foundations | | | | | |
| | 12" thick (labor and material) 17325 sf | 642 | cy | | | |
| | geotextile fabric (+10%) | 54300 | sf | | | |
| 10 | porous fill below slabs on grade | | | | | |
| | 12" thick, crushed stone (labor and material) 27000 sf | 1000 | cy | | | |
| 11 | excavation for storm drainage | | | | | |
| | trenching work | 2600 | cy | | | |
| | backfill work | | | | | |
| | bedding material (3/4" crushed stone) (labor and material) | 1107 | cy | | | |
| | clean fill | 1248 | cy | | | |
| | filter fabric (around stone) (+10%) | 29776 | sf | | | |
| | warning tape (+10%) | 3940 | lf | | | |
| | trench box sheeting | | | | | |
| | 6'-0 wide x 8'-0 high | 205 | lf | | | |
| | note: used detail on dwg CD-503 for roof drains and detail on dwg CD-504 for balance of storm drainage | | | | | |
| 12 | excavation for sewer | | | | | |
| | trenching work | 1087 | cy | | | |
| | backfill work | | | | | |
| | bedding material (3/4" crushed stone) (labor and material) | 128 | cy | | | |
| | sand (labor and material) | 200 | cy | | | |
| | bank run gravel (labor and material) | 655 | cy | | | |
| | clean fill | 89 | cy | | | |
| | warning tape (+10%) | 635 | lf | | | |
| | trench box sheeting | | | | | |
| | 6'-0 wide x 8'-0 high | 340 | lf | | | |

R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208
DEERFIELD BEACH, FL 33442

PO BOX 162
MONTICELLO, NY 12701

TEL. (954)360-9496 FAX (954) 360-9326

PROJECT: WILLOW CREEK APARTMENTS

HARTFORD, CT

MARCH 2018

R & L #12764

MASTER RECAP. SHEET

SHEET NO. 1

OF NO. 4

| NO. | GENERAL DESCRIPTION | QUANTITY | | UNIT LAB. | TOT. LAB. | UNIT MAT. | TOT. MAT. |
|-----|---|----------|----|-----------|-----------|-----------|-----------|
| | SITE IMPROVEMENTS | | | | | | |
| 1 | pavement | | | | | | |
| | a) standard duty | | | | | | |
| | 1 1/2" bit conc, class 2 | | | | | | |
| | tack coat | | | | | | |
| | 2" bit conc, class 1 | | | | | | |
| | 6" processed aggregate base | | | | | | |
| | 10" subbase | 2862 | sy | | | | |
| | b) city of Hartford | | | | | | |
| | 1 1/2" bit conc, class 1 | | | | | | |
| | 3 1/2" bit conc, class 4 | | | | | | |
| | 12" processed traprock | 1604 | sy | | | | |
| | c) temporary drives | | | | | | |
| | 2 1/2" bit conc, class 2 | | | | | | |
| | 10" processed aggregate base | 828 | sy | | | | |
| | d) temporary walks | | | | | | |
| | 2 1/2" bit conc, class 2 | | | | | | |
| | 10" processed aggregate base | 145 | sy | | | | |
| 2 | gravel turn-around (see dwg CE-101) | | | | | | |
| | no detail shown | 7800 | sf | | | | |
| 3 | concrete walks and pads | | | | | | |
| | a) typical | | | | | | |
| | 5" conc | | | | | | |
| | 12" traprock | | | | | | |
| | finish area | | | | | | |
| | scored area | 12295 | sf | | | | |
| | expansion joint filler (1/2" x 5") | 860 | lf | | | | |
| | turned down edge mono (670 lf) one side forms | 784 | sf | | | | |
| | conc | 23 | cy | | | | |
| | detectable warning surface | 162 | sf | | | | |

