

# R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208  
DEERFIELD BEACH, FL 33442

PO BOX 162  
MONTICELLO, NY 12701

TEL. (954)360-9496 FAX (954) 360-9326

PROJECT:

HOPEWELL HIGH SCHOOL

TITUSVILLE, NJ

MAY 2017

R & L #12518

## MASTER RECAP. SHEET

SHEET NO. 1

OF NO. 6

NO.	GENERAL DESCRIPTION	QUANTITY	UNIT LAB.	TOT. LAB.	UNIT MAT.	TOT. MAT.
	<b>SECTION 04200 UNIT MASONRY</b>					
1	face brick (standard size)					
	cavity bond	2468 sf	17276 pcs			
	soldier course	694 sf	4858 pcs			
	on existing walls	306 sf	2142 pcs			
	rollock sills	6 lf	27 pcs			
	reveals	50 sf	350 pcs			
	washdown area	3524	sf			
2	manufactured stone masonry					
	type 1 - 4x16x24					
	stack bond	3390 sf	1272 pcs			
	at panels (stack bond)	934 sf	351 pcs			
	at piers	85 sf	32 pcs			
	type 2 - 4x8x24					
	cavity bond	6851 sf	5139 pcs			
	band course	629 sf	472 pcs			
	band course (at piers)	12 sf	9 pcs			
	running bond (at dumpster)	706 sf	530 pcs			
	washdown area	12607	sf			
	attic stock per specs (5%)					
	type 1		83 pcs			
	type 2		308 pcs			
3	simulated stone veneer (thin set)					
	type 3 (dry stack)					
	piers	2450	sf			
	type 4 (masonry joints)					
	walls	1182	sf			
	exterior walls	964	sf			
	washdown area	4596	sf			

# R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208  
DEERFIELD BEACH, FL 33442

PO BOX 162  
MONTICELLO, NY 12701

TEL. (954)360-9496 FAX (954) 360-9326

PROJECT:

HOPEWELL HIGH SCHOOL

TITUSVILLE, NJ

MAY 2017

R & L #12518

MASTER RECAP. SHEET

SHEET NO. 2

OF NO. 6

NO.	GENERAL DESCRIPTION	QUANTITY	UNIT LAB.	TOT. LAB.	UNIT MAT.	TOT. MAT.
	<b>SECTION 04200 (CONT.)</b>					
4	ground face block					
	at partitions					
	10x8x16 62 sf	70	pcs			
	8x8x16 1653 sf	1860	pcs			
	8x8x16 (finished two sides) 189 sf	213	pcs			
	6x8x16 332 sf	374	pcs			
	6x8x16 (finished three sides) 62 sf	70	pcs			
	6x8x16 (columns) 168 sf	189	pcs			
	4x8x16 252 sf	283	pcs			
	4x8x16 (columns) 124 sf	140	pcs			
	washdown area	2842	sf			
	additional cost for corners	280	pcs			
5	acoustic block					
	as back up					
	10x8x16 1455 sf	1637	pcs			
	as partitions					
	10x8x16 451 sf	507	pcs			
	washdown area	1906	sf			
6	concrete masonry units					
	as back up					
	10x8x16 6412 sf	7214	pcs			
	10x8x16 (bond beam) 380 sf	428	pcs			
	8x8x16 8538 sf	9605	pcs			
	8x8x16 (bond beam) 619 sf	696	pcs			
	8x8x16 (piers) 2092 sf	2354	pcs			
	8x8x16 (at site walls) 333 sf	375	pcs			
	8x8x16 (at dumpster) 517 sf	582	pcs			
	4x8x16 (piers) 64 sf	72	pcs			

# R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208  
DEERFIELD BEACH, FL 33442  
TEL. (954)360-9496

PO BOX 162  
MONTICELLO, NY 12701  
FAX (954) 360-9326

PROJECT:

HOPEWELL HIGH SCHOOL

TITUSVILLE, NJ

MAY 2017

R & L #12518

MASTER RECAP. SHEET

SHEET NO. 3

OF NO. 6

NO.	GENERAL DESCRIPTION	QUANTITY	UNIT LAB.	TOT. LAB.	UNIT MAT.	TOT. MAT.
	<b>SECTION 04200 (CONT.)</b>					
6	concrete masonry units (cont.)					
	additional back up at think set stone					
	6x8x16 293 sf	330	pcs			
	8x8x16 889 sf	1000	pcs			
	behind panels and siding					
	12x8x16 835 sf	939	pcs			
	10x8x16 38 sf	43	pcs			
	8x8x16 2212 sf	2489	pcs			
	8x8x16 (bond beam) 226 sf	254	pcs			
	as partitions					
	10x8x16 4087 sf	4590	pcs			
	10x8x16 (bond beam) 240 sf	270	pcs			
	8x8x16 4647 sf	5228	pcs			
	8x8x16 (bond beam) 322 sf	362	pcs			
	8x8x16 (columns) 130 sf	146	pcs			
	6x8x16 6885 sf	7746	pcs			
	6x8x16 (bond beams) 350 sf	394	pcs			
	6x8x16 (columns) 180 sf	203	pcs			
	4x8x16 640 sf	720	pcs			
	4x8x16 (columns) 552 sf	624	pcs			
	misc. block					
	8x8x16 (in soffets) 245 sf	276	pcs			
	4x8x16 (at flashing) 77 sf	86	pcs			
	partitions in existing building					
	10x8x16 65 sf	73	pcs			
	8x8x16 321 sf	361	pcs			
	8x8x16 (bond beam) 18 sf	20	pcs			
	6x8x16 723 sf	813	pcs			
	6x8x16 (bond beam) 38 sf	43	pcs			
	4x8x16 130 sf	146	pcs			

# R & L CONSTRUCTION SERVICES

1701 W. HILLSBORO BLVD. #208  
DEERFIELD BEACH, FL 33442

PO BOX 162  
MONTICELLO, NY 12701

TEL. (954)360-9496 FAX (954) 360-9326

PROJECT:

HOPEWELL HIGH SCHOOL

TITUSVILLE, NJ

MAY 2017

R & L #12518

MASTER RECAP. SHEET

SHEET NO. 4

OF NO. 6

NO.	GENERAL DESCRIPTION	QUANTITY	UNIT LAB.	TOT. LAB.	UNIT MAT.	TOT. MAT.
	<b>SECTION 04200 (CONT.)</b>					
7	foundation block					
	12x8x16 1098 sf	1235	pcs			
	12x8x16 (piers) 412 sf	464	pcs			
	10x8x16 1361 sf	1531	pcs			
	8x8x16 1484 sf	1670	pcs			
	6x8x16 124 sf	140	pcs			
	4x8x16 1643 sf	1848	pcs			
	as backup					
	12x8x16 232 sf	250	pcs			
	10x8x16 318 sf	358	pcs			
	8x8x16 286 sf	322	pcs			
8	misc. items					
	pole scaffolding exterior	23406	sf			
	pole scaffolding interior	18840	sf			
	dur-o-eye reinforcing 16205 sf	12154	lf			
	wall ties 803 sf	442	pcs			
	wall ties on existing walls 306 sf	168	pcs			
	wall ties for stone	4396	sf			
	durowall reinforcing 38885 sf	29164	lf			
	mortar for face brick	24652	pcs			
	mortar for concrete masonry units	56030	pcs			
	mortar for manufactured stone veneer					
	4x16x24	1655	pcs			
	4x8x24	6150	pcs			
	mortar for ground face block	3199	pcs			
	mortar for acoustic block	2144	pcs			
	mortar for thin set stone	2146	pcs			
	control joints / expansion joints	290	lf			
	rigid insulation (2 1/2")	15836	sf			
	spray applied air/vapor barrier	15836	sf			





